



ACT OF JSC UKRELEKTROMASH DATED 18.01.2001

Compressor 2VM 4-24/9 M-1: output rose and holds up under load

JSC Ukrelektromash, Kharkiv Electrical Engineering Plant · boiler and compressor section · approved by the plant's technical director F. F. Laptsevich

Kharkiv, Ukraine · contract No. 91-P dated 01.12.2000 · measurements on 08.12.2000 and 18.01.2001

PRODUCT	TEST OBJECT	DOCUMENT TYPE
XADO compound restorative repair by XADO technology® · contract No. 91-P dated 01.12.2000	Piston compressor 2VM 4-24/9 M-1 compressor No. 8 of the boiler and compressor section · 3 m ³ receiver, working pressure 8 atm	Technical act, signed by both parties seal and the technical director's «Approved» endorsement

EQUIPMENT	OPERATING CONDITIONS	WHAT WAS MEASURED
Piston compressor 2VM 4-24/9 M-1, No. 8	Boiler and compressor section of the plant, 3 m ³ receiver, working pressure 8 atm	Time to build working pressure from 0 to 8 atm

The compressor ran in the section's normal duty: the «before» measurement on 08.12.2000, the «after» measurement at 400 hours of operation, on 18.01.2001.

Key result

↑ **60 %**

compressor output, build-up to 8 atm: 1 min 36 s → 1 min 00 s

Measurements before and after the restorative repair

PARAMETER	BEFORE REPAIR, 08.12.2000	AFTER, 400 h OF OPERATION
Time to build working pressure from 0 to 8 atm	1 min 36 s	1 min 00 s
Compressor output by filling of the 3 m ³ receiver	100 %	160 %

Output was determined from the time to fill the 3 m³ receiver to 8 atm; the standard instruments and sensors of the compressor unit were used for the measurements.

Conclusion of the plant commission

The commission of JSC Ukrelektromash — the deputy chief engineer, the head of the maintenance and repair shop, and the foreman of the boiler and compressor section — recorded: after the restorative repair of the compressor 2VM 4-24/9 M-1 by XADO technology® using the XADO compound, the time to build working pressure in the 3 m³ receiver fell from **1 min 36 s** to **1 min 00 s**. The «after» measurement was taken at **400 hours** of operation, so the effect holds on a working machine, not only in the first hours after treatment. The act's conclusion verbatim: «The results obtained indicate the expediency of carrying out restorative repair by XADO technology® on all industrial equipment» of the plant. The act was approved by the plant's technical director under seal.

XADO

© XADO. All rights reserved.

The results relate to the piston compressor 2VM 4-24/9 M-1 of the boiler and compressor section of JSC Ukrelektromash and to the duty of filling a 3 m³ receiver to 8 atm; on other equipment and in other duties the figures may differ. The original act with signatures and seal is published in full and available for download.